

INTERNAL COST SHEET · REF NF-2026-0928 · 28/09/2026

Flooring, Bespoke Joinery & Lighting Package

Marina Gate 2 — Unit 2304 · Mr. Ahmed Khan · Dubai Marina, Dubai

SELLING PRICE · NET EX VAT AED 81,950 10 scope items	DIRECT COST AED 39,479.36 Incl. overhead 49,313	GROSS PROFIT · MARGIN AED 42,470.64 51.8% · ON TARGET	NET PROFIT · AFTER OVERHEAD AED 32,636.64 39.8% · ON TARGET	MARKUP ON COST 107.6% on direct cost	VAT AED 4,097.50 5% · registered	GRAND TOTAL AED 86,047.50 Client pays, incl. VAT
---	---	--	--	--	--	--

Target margin 35% · minimum 25% · overhead 12% · contingency 5% (AED 3,892.65) included in the scope amounts

WARNINGS (3)

- 'SPC Flooring': AED 457 per m² is outside the usual Dubai range 60–220 — check quantities and rates
- 61 rate(s) are still placeholders — confirm them with `rates.py placeholders` before sending this quote
- Item 01: AED 457 per m² is outside the usual Dubai range 60–220 — check quantities and rates

ASSUMPTIONS (0)

No assumptions recorded.

Scope summary

AMOUNTS IN AED · MARGIN = PROFIT / CLIENT AMOUNT

NO	ITEM	COST MATERIALS	COST LABOUR	COST OTHER	COST TOTAL	CLIENT AMOUNT	PROFIT	MARGIN
01	SPC Flooring All dry areas	9,877.24	770.26	0.00	13,069.07	34,350.00	21,280.93	62.0%
02	Living Room Wall Cladding Living Room	1,465.72	328.84	0.00	2,202.69	3,550.00	1,347.31	38.0%
03	TV Unit Living Room	2,273.05	861.12	0.00	3,846.98	6,600.00	2,753.02	41.7%
04	Cove Lighting Living Room, Master Bedroom	1,404.30	1,749.16	0.00	3,870.65	7,700.00	3,829.35	49.7%
05	Master Bedroom Set Master Bedroom	2,168.36	1,034.85	0.00	3,931.73	6,900.00	2,968.27	43.0%
06	Built-in Wardrobes	2,998.15	2,047.43	0.00	6,193.10	11,550.00	5,356.90	46.4%
07	Dresser & Vanity Mirror Master Bedroom	804.93	517.25	0.00	1,622.88	3,000.00	1,377.12	45.9%
08	Gypsum Partition Living Room	202.87	176.52	0.00	465.68	850.00	384.32	45.2%

NO	ITEM	COST MATERIALS	COST LABOUR	COST OTHER	COST TOTAL	CLIENT AMOUNT	PROFIT	MARGIN
09	Electrical Points	685.86	498.96	90.00	1,564.75	3,100.00	1,535.25	49.5%
10	Painting Whole apartment	1,141.41	1,067.94	0.00	2,711.83	4,350.00	1,638.17	37.7%
Total		23,021.89	9,052.33	90.00	39,479.36	81,950.00	42,470.64	51.8%

Item costs are the direct take-off per item; consumables, stock rounding and preliminaries sit in the cost bridge.

Cost bridge

DIRECT COST, OVERHEAD AND PROFIT

COST BRIDGE	AED
Materials	23,021.89
Labour	9,052.32
Other	90.00
Consumables	690.66
Stock rounding (buying full packs and sheets)	688.13
Preliminaries	4,707.11
= Direct cost	39,479.36
+ Overhead (12% of direct cost)	9,834.00
= Total cost	49,313.36
Contingency (5%) carried inside the scope amounts	3,892.65
Check: parts sum to 38,250.11, not the direct cost (difference 1,229.25).	

PRICE & PROFIT	AED	MARGIN
Scope amounts (subtotal)	81,950.00	
= Selling price, net ex VAT	81,950.00	
VAT 5%	4,097.50	
= Grand total to client	86,047.50	
Gross profit (net sell — direct cost)	42,470.64	51.8%
Net profit (after overhead)	32,636.64	39.8%
Markup on direct cost		107.6%

• PLACEHOLDER PRICES STILL IN USE (61)

These rates are rate-book defaults, not your supplier prices. Replace them with real quotes before sending the quotation: the cost, margin and purchase totals below depend on them.

REF	DESCRIPTION	UNIT	PLACEHOLDER RATE	PURCHASE COST	USED IN ITEMS
adjustable_leg	Adjustable cabinet leg	pc	4.00	56.00	06
back_box	GI back box 3 x 3	pc	1.75	10.50	09
batting	Polyester batting / wadding	m2	8.00	23.20	05
bed_gas_lift	Bed gas-lift mechanism (pair)	set	150.00	150.00	05
cable_1_5	Single-core cable 1.5 mm² (coil 91.4 m)	m	1.53	91.80	02, 03, 04, 06, 07

• PLACEHOLDER PRICES STILL IN USE (61)

These rates are rate-book defaults, not your supplier prices. Replace them with real quotes before sending the quotation: the cost, margin and purchase totals below depend on them.

REF	DESCRIPTION	UNIT	PLACEHOLDER RATE	PURCHASE COST	USED IN ITEMS
cable_2_5	Single-core cable 2.5 mm ² (coil 91.4 m)	m	2.19	315.36	09
cable_grommet	Cable grommet	pc	5.00	10.00	03
carpenter	Carpenter (workshop)	h	21.60	—	03, 05, 06, 07
cladding_adhesive	Panel adhesive cartridge	pc	18.00	360.00	02, 03, 05
cladding_trim	WPC / aluminium trim 2.9 m	pc	18.00	108.00	02
conduit_20	PVC conduit 20 mm x 3 m	pc	7.50	127.50	03, 09
drawer_runner	Soft-close full-extension runner (pair)	pair	45.00	360.00	03, 05, 07
drywall_screws	Drywall screws 25 mm	pc	0.04	30.96	04, 08
edge_band_thick	PVC edge band 2 mm (fronts)	m	1.40	118.72	03, 05, 06, 07
edge_band_thin	PVC edge band 0.8 mm (carcass)	m	0.55	43.12	03, 05, 06, 07
electrician	Electrician	h	21.60	—	02, 03, 04, 06, 07, 09
floating_bracket	Concealed floating-shelf bracket	pc	25.00	100.00	03
flooring	Flooring installer	h	19.90	—	01
foam_50mm	High-density foam 50 mm	m ²	42.50	114.75	05
furring_channel	Furring channel 3 m	pc	9.10	418.60	04
gypsum	Gypsum carpenter	h	19.90	—	04, 08
gypsum_board_std	Gypsum board 1200 x 2400 x 12.5 mm	sheet	22.00	352.00	04, 08
handle_std	Bar handle 160 mm	pc	15.00	225.00	05, 06, 07
hanging_rail	Oval wardrobe rail	m	15.00	37.50	06
hinge_soft_close	Soft-close concealed hinge	pc	15.00	675.00	06
installer	Joinery installer	h	23.40	—	02, 03, 05, 06, 07
joint_compound	Joint compound 28 kg	bag	57.50	57.50	04, 08
joint_tape	Paper joint tape	m	0.23	10.72	04, 08
led_connector_kit	LED feed connector / end caps / clips kit	pc	6.00	60.00	02, 03, 04, 06, 07
led_driver_100w	LED driver 24 V 100 W	pc	60.00	60.00	06
led_driver_300w	LED driver 24 V 300 W	pc	130.00	260.00	04
led_driver_60w	LED driver 24 V 60 W	pc	40.00	120.00	02, 03, 07
led_profile	Aluminium LED profile + diffuser 2 m	pc	20.00	160.00	02, 03, 06
led_sensor	Touch / door sensor switch	pc	25.00	50.00	06, 07
led_strip_24v	LED strip 24 V 10 W/m 3000K	m	9.00	540.00	02, 03, 04, 06, 07

• PLACEHOLDER PRICES STILL IN USE (61)

These rates are rate-book defaults, not your supplier prices. Replace them with real quotes before sending the quotation: the cost, margin and purchase totals below depend on them.

REF	DESCRIPTION	UNIT	PLACEHOLDER RATE	PURCHASE COST	USED IN ITEMS
mdf_06	MDF 6 mm 1220 x 2440 (backs, drawer bottoms)	sheet	35.00	280.00	03, 05, 06, 07
mfc_18	Egger MFC 18 mm 2800 x 2070	sheet	250.00	2,750.00	03, 05, 06, 07
mirror_adhesive	Mirror adhesive cartridge	pc	25.00	50.00	07
mirror_clear_5mm	Clear silver mirror 5 mm	m2	80.00	96.00	07
mirror_edge_polish	Mirror edge polishing	m	7.00	29.40	07
paint_ceiling	Ceiling emulsion matt	l	8.50	153.00	10
paint_emulsion	Interior emulsion (Jotun Fenomastic class)	l	15.60	1,123.20	10
painter	Painter	h	17.50	—	10
ply_12	Plywood 12 mm 1220 x 2440	sheet	85.00	85.00	05
ply_18	Marine plywood 18 mm 1220 x 2440	sheet	120.00	240.00	05
pvc_marble_sheet	PVC marble sheet 1220 x 2800 x 3 mm	sheet	170.00	680.00	05
pvc_trim	PVC / aluminium edge trim 2.9 m	pc	18.00	180.00	03, 05
shelf_pin	Shelf support pin	pc	0.30	12.00	06
skirting_pvc_80	PVC skirting 80 mm (2.4 m)	pc	29.00	1,015.00	01
socket_double_13a	13 A twin switched socket	pc	40.00	240.00	09
stone_pvc_panel	Stone-finish PU/PVC panel 1200 x 600 mm	pc	85.00	1,105.00	03
stud_c	Metal C-stud 70 mm x 3 m	pc	10.00	50.00	08
threshold_profile	Aluminium threshold / transition profile 0.9 m	pc	30.00	120.00	01
timber_batten	Timber batten 25 x 50 mm	m	3.50	39.20	05
track_u	Metal U-track 72 mm x 3 m	pc	9.50	19.00	08
tv_bracket	TV wall bracket (fixed/tilt)	pc	120.00	120.00	03
upholsterer	Upholsterer (workshop)	h	21.60	—	05
upholstery_fabric	Upholstery fabric 140 cm	m	45.00	135.00	05
wall_hanger	Concealed cabinet wall hanger	pc	12.00	132.00	03, 05
wall_putty	Wall putty 20 kg	bag	35.00	140.00	10
wpc_fluted_panel	WPC fluted panel 160 x 2900 mm	pc	35.00	1,085.00	02

Line build-up by scope item

TAKE-OFF, COST AND SELL PER LINE · AMOUNTS IN AED

01 SPC Flooring · All dry areas						Client AED 34,350 · Cost 13,069.07 · Profit 21,280.93 · Margin 62.0%			
KIND	DESCRIPTION	CALC (TAKE-OFF)	QTY	UNIT	UNIT COST	COST	UNIT SELL	SELL	
MATERIAL	SPC flooring plank 1800 x 180 mm spc_plank	75.18 m² x (1 + 8% waste) / 0.324 m² per plank = 250.6	250.6	plank	35.00	8,771.00	110.00	27,566.00	
MATERIAL	PVC skirting 80 mm (2.4 m) skirting_pvc_80 · PLACEHOLDER	perimeter 77.8 m - doors 3.6 m = 74.2 lm + 10% waste	34.01	pc	29.00	986.24	40.60	1,380.74	
MATERIAL	Aluminium threshold / transition profile 0.9 m threshold_profile · PLACEHOLDER	4 door openings	4	pc	30.00	120.00	42.00	168.00	
LABOUR	Flooring installer flooring · PLACEHOLDER	75.18 m² x 0.32 h/m² +10% site access allowance (included in material resale price)	26.46	h	19.90	526.62	0.00	0.00	
LABOUR	Flooring installer flooring · PLACEHOLDER	skirting 74.2 lm x 0.15 h/lm +10% site access allowance (included in material resale price)	12.24	h	19.90	243.64	0.00	0.00	
Line totals						10,647.50		29,114.74	

Item cost total 13,069.07 · materials 9,877.24 · labour 770.26 · sell build-up 29,114.74 · client amount 34,350.00

Labour hours: flooring 38.7 h

Warnings: AED 457 per m² is outside the usual Dubai range 60–220 — check quantities and rates

02 Living Room Wall Cladding · Living Room						Client AED 3,550 · Cost 2,202.69 · Profit 1,347.31 · Margin 38.0%			
KIND	DESCRIPTION	CALC (TAKE-OFF)	QTY	UNIT	UNIT COST	COST	UNIT SELL	SELL	
MATERIAL	WPC fluted panel 160 x 2900 mm wpc_fluted_panel · PLACEHOLDER	4.5 m / 0.16 m = 29 columns x 1 full pc + 5% waste, rounded per wall	31	pc	35.00	1,085.00	50.75	1,573.25	
MATERIAL	WPC / aluminium trim 2.9 m cladding_trim · PLACEHOLDER	perimeter 14.6 lm + 10%	5.54	pc	18.00	99.68	26.10	144.54	
LABOUR	Joinery installer installer · PLACEHOLDER	trims 14.6 lm +10% site access allowance	2.41	h	23.40	56.37	60.00	144.54	
MATERIAL	Panel adhesive cartridge cladding_adhesive · PLACEHOLDER	12.6 m² x 0.6 per m²	7.56	pc	18.00	136.08	26.10	197.32	
LABOUR	Joinery installer installer · PLACEHOLDER	12.6 m² x 0.65 h/m² +10% site access allowance	9.01	h	23.40	210.81	60.00	540.54	
MATERIAL	LED strip 24 V 10 W/m 3000K led_strip_24v · PLACEHOLDER	4.5 m x 1 run(s) + 5% = 4.73 m	4.72	m	9.00	42.53	14.40	68.04	
MATERIAL	LED driver 24 V 60 W led_driver_60w · PLACEHOLDER	45 W (4.5 m x 10 W/m) at 80% max load	1	pc	40.00	40.00	64.00	64.00	
MATERIAL	Aluminium LED profile + diffuser 2 m led_profile · PLACEHOLDER	4.5 m + 5%	2.36	pc	20.00	47.25	32.00	75.60	
MATERIAL	LED feed connector / end caps / clips kit led_connector_kit · PLACEHOLDER	1 feed point(s)	1	pc	6.00	6.00	9.60	9.60	
MATERIAL	Single-core cable 1.5 mm² (coil 91.4 m) cable_1_5 · PLACEHOLDER	1 feeds x 6 m	6	m	1.53	9.18	2.45	14.69	
LABOUR	Electrician electrician · PLACEHOLDER	4.73 m strip, 1 driver(s) +10% site access allowance	2.85	h	21.60	61.66	60.00	171.27	
Line totals						1,794.56		3,003.39	
Item cost total 2,202.69 · materials 1,465.72 · labour 328.84 · sell build-up 3,003.38 · client amount 3,550.00									
Labour hours: installer 11.4 h, electrician 2.9 h									

03 TV Unit · Living Room						Client AED 6,600 · Cost 3,846.98 · Profit 2,753.02 · Margin 41.7%		
KIND	DESCRIPTION	CALC (TAKE-OFF)	QTY	UNIT	UNIT COST	COST	UNIT SELL	SELL
MATERIAL	Egger MFC 18 mm 2800 x 2070 mfc_18 · PLACEHOLDER	base box x1: 6.55 m² of parts / (5.8 m² sheet x 84% yield)	1.34	sheet	250.00	336.36	375.00	504.54
MATERIAL	MDF 6 mm 1220 x 2440 (backs, drawer bottoms) mdf_06 · PLACEHOLDER	base box x1: 2.35 m² of parts / (2.98 m² sheet x 85% yield)	0.93	sheet	35.00	32.53	52.50	48.80
MATERIAL	PVC edge band 0.8 mm (carcass) edge_band_thin · PLACEHOLDER	14.48 m carcass edges + 10%	15.93	m	0.55	8.76	0.83	13.14
MATERIAL	PVC edge band 2 mm (fronts) edge_band_thick · PLACEHOLDER	7.44 m front edges + 10%	8.18	m	1.40	11.46	2.10	17.19
MATERIAL	Soft-close full-extension runner (pair) drawer_runner · PLACEHOLDER	2 drawers	2	pair	45.00	90.00	67.50	135.00
MATERIAL	Concealed cabinet wall hanger wall_hanger · PLACEHOLDER	floating: 7 concealed hangers	7	pc	12.00	84.00	18.00	126.00
LABOUR	Carpenter (workshop) carpenter · PLACEHOLDER	1 x (2 setup + 8.9 m² x 1.0 + 0 doors x 1.0 + 2 drawers x 1.5 + 0 shelves x 0.3)	13.9	h	21.60	300.29	55.00	764.63
LABOUR	Joinery installer installer · PLACEHOLDER	1 x (1.5 + 3 m x 1.5 h/m) x 1.3 wall-hung +10% site access allowance	8.58	h	23.40	200.77	60.00	514.80
MATERIAL	Stone-finish PU/PVC panel 1200 x 600 mm stone_pvc_panel · PLACEHOLDER	8.4 m² x (1 + 8%) / 0.72 m² per sheet	13	pc	85.00	1,105.00	123.25	1,602.25
MATERIAL	PVC / aluminium edge trim 2.9 m pvc_trim · PLACEHOLDER	perimeter 11.6 lm + 10%	4.4	pc	18.00	79.20	26.10	114.84
LABOUR	Joinery installer installer · PLACEHOLDER	trims 11.6 lm +10% site access allowance	1.91	h	23.40	44.79	60.00	114.84
MATERIAL	Panel adhesive cartridge cladding_adhesive · PLACEHOLDER	8.4 m² x 0.6 per m²	5.04	pc	18.00	90.72	26.10	131.54
LABOUR	Joinery installer installer · PLACEHOLDER	8.4 m² x 0.7 h/m² +10% site access allowance	6.47	h	23.40	151.35	60.00	388.08
MATERIAL	Egger MFC 18 mm 2800 x 2070 mfc_18 · PLACEHOLDER	2 floating shelves: 1.37 m² of parts / (5.8 m² sheet x 84% yield)	0.28	sheet	250.00	70.35	375.00	105.52
MATERIAL	PVC edge band 2 mm (fronts) edge_band_thick · PLACEHOLDER	shelf edges	6.38	m	1.40	8.93	2.10	13.40
MATERIAL	Concealed floating-shelf bracket floating_bracket · PLACEHOLDER	2 shelves x 2 concealed brackets	4	pc	25.00	100.00	37.50	150.00
LABOUR	Carpenter (workshop) carpenter · PLACEHOLDER	2 shelves	3	h	21.60	64.80	55.00	165.00

03 TV Unit · Living Room						Client AED 6,600 · Cost 3,846.98 · Profit 2,753.02 · Margin 41.7%		
KIND	DESCRIPTION	CALC (TAKE-OFF)	QTY	UNIT	UNIT COST	COST	UNIT SELL	SELL
LABOUR	Joinery installer installer · PLACEHOLDER	2 shelves +10% site access allowance	1.65	h	23.40	38.61	60.00	99.00
MATERIAL	LED strip 24 V 10 W/m 3000K led_strip_24v · PLACEHOLDER	1.2 m x 2 run(s) + 5% = 2.52 m	2.52	m	9.00	22.68	14.40	36.29
MATERIAL	LED driver 24 V 60 W led_driver_60w · PLACEHOLDER	24 W (2.4 m x 10 W/m) at 80% max load	1	pc	40.00	40.00	64.00	64.00
MATERIAL	Aluminium LED profile + diffuser 2 m led_profile · PLACEHOLDER	2.4 m + 5%	1.26	pc	20.00	25.20	32.00	40.32
MATERIAL	LED feed connector / end caps / clips kit led_connector_kit · PLACEHOLDER	2 feed point(s)	2	pc	6.00	12.00	9.60	19.20
MATERIAL	Single-core cable 1.5 mm² (coil 91.4 m) cable_1_5 · PLACEHOLDER	2 feeds x 6 m	12	m	1.53	18.36	2.45	29.38
LABOUR	Electrician electrician · PLACEHOLDER	2.52 m strip, 1 driver(s) +10% site access allowance	1.91	h	21.60	41.20	60.00	114.44
MATERIAL	TV wall bracket (fixed/tilt) tv_bracket · PLACEHOLDER	TV wall bracket	1	pc	120.00	120.00	180.00	180.00
LABOUR	Joinery installer installer · PLACEHOLDER	TV bracket +10% site access allowance	0.82	h	23.40	19.30	60.00	49.50
MATERIAL	Cable grommet cable_grommet · PLACEHOLDER	cable grommets	2	pc	5.00	10.00	7.50	15.00
MATERIAL	PVC conduit 20 mm x 3 m conduit_20 · PLACEHOLDER	concealed cable route	1	pc	7.50	7.50	12.00	12.00
Line totals						3,134.16		5,568.70
Item cost total 3,846.98 · materials 2,273.05 · labour 861.12 · sell build-up 5,568.70 · client amount 6,600.00 Labour hours: carpenter 16.9 h, installer 19.4 h, electrician 1.9 h								

04 Cove Lighting · Living Room, Master Bedroom						Client AED 7,700 · Cost 3,870.65 · Profit 3,829.35 · Margin 49.7%		
KIND	DESCRIPTION	CALC (TAKE-OFF)	QTY	UNIT	UNIT COST	COST	UNIT SELL	SELL
MATERIAL	LED strip 24 V 10 W/m 3000K led_strip_24v · PLACEHOLDER	21.4 m x 1 run(s) + 5% = 22.47 m	22.47	m	9.00	202.23	14.40	323.57
MATERIAL	LED driver 24 V 300 W led_driver_300w · PLACEHOLDER	214 W (21.4 m x 10 W/m) at 80% max load	1	pc	130.00	130.00	208.00	208.00
MATERIAL	LED feed connector / end caps / clips kit led_connector_kit · PLACEHOLDER	3 feed point(s)	3	pc	6.00	18.00	9.60	28.80
MATERIAL	Single-core cable 1.5 mm² (coil 91.4 m) cable_1_5 · PLACEHOLDER	3 feeds x 6 m	18	m	1.53	27.54	2.45	44.06
LABOUR	Electrician electrician · PLACEHOLDER	22.47 m strip, 1 driver(s) +10% site access allowance	5.77	h	21.60	124.60	60.00	346.10
MATERIAL	LED strip 24 V 10 W/m 3000K led_strip_24v · PLACEHOLDER	17.2 m x 1 run(s) + 5% = 18.06 m	18.06	m	9.00	162.54	14.40	260.06
MATERIAL	LED driver 24 V 300 W led_driver_300w · PLACEHOLDER	172 W (17.2 m x 10 W/m) at 80% max load	1	pc	130.00	130.00	208.00	208.00
MATERIAL	LED feed connector / end caps / clips kit led_connector_kit · PLACEHOLDER	2 feed point(s)	2	pc	6.00	12.00	9.60	19.20
MATERIAL	Single-core cable 1.5 mm² (coil 91.4 m) cable_1_5 · PLACEHOLDER	2 feeds x 6 m	12	m	1.53	18.36	2.45	29.38
LABOUR	Electrician electrician · PLACEHOLDER	18.06 m strip, 1 driver(s) +10% site access allowance	4.8	h	21.60	103.64	60.00	287.89
MATERIAL	Gypsum board 1200 x 2400 x 12.5 mm gypsum_board_std · PLACEHOLDER	cove: 38.6 lm x 0.7 m girth + 15%	10.79	sheet	22.00	237.36	29.70	320.44
MATERIAL	Furring channel 3 m furring_channel · PLACEHOLDER	cove framing 3.5 m per lm	45.03	pc	9.10	409.80	12.29	553.23
MATERIAL	Drywall screws 25 mm drywall_screws · PLACEHOLDER	cove: 27.02 m² x 18 screws/m²	486.36	pc	0.04	21.89	0.06	29.55
MATERIAL	Paper joint tape joint_tape · PLACEHOLDER	cove: 27.02 m² x 1.1 m/m²	29.72	m	0.23	6.84	0.31	9.23
MATERIAL	Joint compound 28 kg joint_compound · PLACEHOLDER	cove: 27.02 m² x 0.5 kg/m²	0.48	bag	57.50	27.74	77.62	37.45
LABOUR	Gypsum carpenter gypsum · PLACEHOLDER	38.6 lm x 1.8 h/lm +10% site access allowance	76.43	h	19.90	1,520.92	50.00	3,821.40
Line totals						3,153.46		6,526.36

04 Cove Lighting · Living Room, Master Bedroom

Client AED 7,700 · Cost 3,870.65 · Profit 3,829.35 · Margin 49.7%

KIND	DESCRIPTION	CALC (TAKE-OFF)	QTY	UNIT	UNIT COST	COST	UNIT SELL	SELL
------	-------------	-----------------	-----	------	-----------	------	-----------	------

Item cost total 3,870.65 · materials 1,404.30 · labour 1,749.16 · sell build-up 6,526.37 · client amount 7,700.00
Labour hours: electrician 10.6 h, gypsum 76.4 h
Notes: Cove per room perimeter (Living Room 21.4 m, Master Bedroom 17.2 m), one circuit each

05 Master Bedroom Set · Master Bedroom

Client AED 6,900 · Cost 3,931.73 · Profit 2,968.27 · Margin 43.0%

KIND	DESCRIPTION	CALC (TAKE-OFF)	QTY	UNIT	UNIT COST	COST	UNIT SELL	SELL
------	-------------	-----------------	-----	------	-----------	------	-----------	------

MATERIAL	Egger MFC 18 mm 2800 x 2070 mfc_18 · PLACEHOLDER	nightstand x2: 2.1 m² of parts / (5.8 m² sheet x 84% yield)	0.43	sheet	250.00	107.78	375.00	161.67
MATERIAL	MDF 6 mm 1220 x 2440 (backs, drawer bottoms) mdf_06 · PLACEHOLDER	nightstand x2: 0.76 m² of parts / (2.98 m² sheet x 85% yield)	0.3	sheet	35.00	10.49	52.50	15.73
MATERIAL	PVC edge band 0.8 mm (carcass) edge_band_thin · PLACEHOLDER	6.88 m carcass edges + 10%	7.57	m	0.55	4.16	0.83	6.24
MATERIAL	PVC edge band 2 mm (fronts) edge_band_thick · PLACEHOLDER	2.72 m front edges + 10%	2.99	m	1.40	4.19	2.10	6.28
MATERIAL	Soft-close full-extension runner (pair) drawer_runner · PLACEHOLDER	2 drawers	2	pair	45.00	90.00	67.50	135.00
MATERIAL	Bar handle 160 mm handle_std · PLACEHOLDER	2 fronts	2	pc	15.00	30.00	22.50	45.00
MATERIAL	Concealed cabinet wall hanger wall_hanger · PLACEHOLDER	floating: 4 concealed hangers	4	pc	12.00	48.00	18.00	72.00
LABOUR	Carpenter (workshop) carpenter · PLACEHOLDER	2 x (2 setup + 1.43 m² x 1.0 + 0 doors x 1.0 + 1 drawers x 1.5 + 0 shelves x 0.3)	9.86	h	21.60	212.91	55.00	542.13
LABOUR	Joinery installer installer · PLACEHOLDER	2 x (0.75 + 0.5 m x 0.5 h/m) x 1.3 wall-hung +10% site access allowance	2.86	h	23.40	66.92	60.00	171.60
MATERIAL	Plywood 12 mm 1220 x 2440 ply_12 · PLACEHOLDER	headboard backing: 2.52 m² of parts / (2.98 m² sheet x 85% yield)	1	sheet	85.00	84.65	127.50	126.98
MATERIAL	Timber batten 25 x 50 mm timber_batten · PLACEHOLDER	frame 11.2 lm	11.2	m	3.50	39.20	5.08	56.84
MATERIAL	High-density foam 50 mm foam_50mm · PLACEHOLDER	2.4 m² + 10%	2.64	m2	42.50	112.20	63.75	168.30
MATERIAL	Polyester batting / wadding batting · PLACEHOLDER	2.4 m² + 20% wrap	2.88	m2	8.00	23.04	12.00	34.56
MATERIAL	Upholstery fabric 140 cm upholstery_fabric · PLACEHOLDER	(2+0.3) x (1.2+0.3) m / 1.4 m wide + 20%	2.96	m	45.00	133.07	67.50	199.61
LABOUR	Upholsterer (workshop) upholsterer · PLACEHOLDER	1 x (2 + 2.4 m² x 1.7) x 1.4 (channel)	8.51	h	21.60	183.86	55.00	468.16

05 Master Bedroom Set · Master Bedroom						Client AED 6,900 · Cost 3,931.73 · Profit 2,968.27 · Margin 43.0%		
KIND	DESCRIPTION	CALC (TAKE-OFF)	QTY	UNIT	UNIT COST	COST	UNIT SELL	SELL
LABOUR	Carpenter (workshop) carpenter · PLACEHOLDER	backing frame	2.5	h	21.60	54.00	55.00	137.50
LABOUR	Joinery installer installer · PLACEHOLDER	wall fixing +10% site access allowance	1.65	h	23.40	38.61	60.00	99.00
MATERIAL	Egger MFC 18 mm 2800 x 2070 mfc_18 · PLACEHOLDER	bed box sides, ends, centre rail: 3.53 m² of parts / (5.8 m² sheet x 84% yield)	0.73	sheet	250.00	181.52	375.00	272.28
MATERIAL	Marine plywood 18 mm 1220 x 2440 ply_18 · PLACEHOLDER	mattress platform: 3.99 m² of parts / (2.98 m² sheet x 80% yield)	1.68	sheet	120.00	201.05	180.00	301.58
MATERIAL	MDF 6 mm 1220 x 2440 (backs, drawer bottoms) mdf_06 · PLACEHOLDER	storage base: 3.99 m² of parts / (2.98 m² sheet x 85% yield)	1.58	sheet	35.00	55.19	52.50	82.79
MATERIAL	Bed gas-lift mechanism (pair) bed_gas_lift · PLACEHOLDER	gas lift mechanism (pair)	1	set	150.00	150.00	225.00	225.00
LABOUR	Carpenter (workshop) carpenter · PLACEHOLDER	bed box fabrication	10	h	21.60	216.00	55.00	550.00
LABOUR	Joinery installer installer · PLACEHOLDER	assembly on site +10% site access allowance	2.2	h	23.40	51.48	60.00	132.00
MATERIAL	PVC marble sheet 1220 x 2800 x 3 mm pvc_marble_sheet · PLACEHOLDER	11.2 m² x (1 + 10%) / 3.42 m² per sheet	4	sheet	170.00	680.00	246.50	986.00
MATERIAL	PVC / aluminium edge trim 2.9 m pvc_trim · PLACEHOLDER	perimeter 13.6 lm + 10%	5.16	pc	18.00	92.86	26.10	134.64
LABOUR	Joinery installer installer · PLACEHOLDER	trims 13.6 lm +10% site access allowance	2.24	h	23.40	52.51	60.00	134.64
MATERIAL	Panel adhesive cartridge cladding_adhesive · PLACEHOLDER	11.2 m² x 0.6 per m²	6.72	pc	18.00	120.96	26.10	175.39
LABOUR	Joinery installer installer · PLACEHOLDER	11.2 m² x 0.55 h/m² +10% site access allowance	6.78	h	23.40	158.56	60.00	406.56
Line totals						3,203.21		5,847.48
Item cost total 3,931.73 · materials 2,168.36 · labour 1,034.85 · sell build-up 5,847.49 · client amount 6,900.00								
Labour hours: carpenter 22.4 h, installer 15.7 h, upholsterer 8.5 h								

06 Built-in Wardrobes					Client AED 11,550 · Cost 6,193.10 · Profit 5,356.90 · Margin 46.4%			
Kind	Description	Calc (Take-off)	Qty	Unit	Unit Cost	Cost	Unit Sell	Sell
MATERIAL	Egger MFC 18 mm 2800 x 2070 mfc_18 · PLACEHOLDER	wardrobe x1: 17.65 m² of parts / (5.8 m² sheet x 84% yield)	3.63	sheet	250.00	906.44	375.00	1,359.66
MATERIAL	MDF 6 mm 1220 x 2440 (backs, drawer bottoms) mdf_06 · PLACEHOLDER	wardrobe x1: 6 m² of parts / (2.98 m² sheet x 85% yield)	2.37	sheet	35.00	82.99	52.50	124.49
MATERIAL	PVC edge band 0.8 mm (carcass) edge_band_thin · PLACEHOLDER	22 m carcass edges + 10%	24.2	m	0.55	13.31	0.83	19.97
MATERIAL	PVC edge band 2 mm (fronts) edge_band_thick · PLACEHOLDER	29.8 m front edges + 10%	32.78	m	1.40	45.89	2.10	68.84
MATERIAL	Soft-close concealed hinge hinge_soft_close · PLACEHOLDER	5 doors x 5 hinges (2.5 m high)	25	pc	15.00	375.00	22.50	562.50
MATERIAL	Bar handle 160 mm handle_std · PLACEHOLDER	5 fronts	5	pc	15.00	75.00	22.50	112.50
MATERIAL	Shelf support pin shelf_pin · PLACEHOLDER	6 shelves x 4 pins	24	pc	0.30	7.20	0.45	10.80
MATERIAL	Oval wardrobe rail hanging_rail · PLACEHOLDER	1.6 m rail	1.6	m	15.00	24.00	22.50	36.00
MATERIAL	Adjustable cabinet leg adjustable_leg · PLACEHOLDER	8 adjustable legs	8	pc	4.00	32.00	6.00	48.00
MATERIAL	LED strip 24 V 10 W/m 3000K led_strip_24v · PLACEHOLDER	7.2 m x 1 run(s) + 5% = 7.56 m	7.56	m	9.00	68.04	14.40	108.86
MATERIAL	LED driver 24 V 100 W led_driver_100w · PLACEHOLDER	72 W (7.2 m x 10 W/m) at 80% max load	1	pc	60.00	60.00	96.00	96.00
MATERIAL	Aluminium LED profile + diffuser 2 m led_profile · PLACEHOLDER	7.2 m + 5%	3.78	pc	20.00	75.60	32.00	120.96
MATERIAL	LED feed connector / end caps / clips kit led_connector_kit · PLACEHOLDER	1 feed point(s)	1	pc	6.00	6.00	9.60	9.60
MATERIAL	Single-core cable 1.5 mm² (coil 91.4 m) cable_1_5 · PLACEHOLDER	1 feeds x 6 m	6	m	1.53	9.18	2.45	14.69
LABOUR	Electrician electrician · PLACEHOLDER	7.56 m strip, 1 driver(s) +10% site access allowance	4.07	h	21.60	87.96	60.00	244.33
MATERIAL	Touch / door sensor switch led_sensor · PLACEHOLDER	door / touch sensor	1	pc	25.00	25.00	40.00	40.00
LABOUR	Carpenter (workshop) carpenter · PLACEHOLDER	1 x (5 setup + 23.65 m² x 1.0 + 5 doors x 1.0 + 0 drawers x 1.5 + 6 shelves x 0.3)	35.45	h	21.60	765.77	55.00	1,949.89

06 Built-in Wardrobes			Client AED 11,550 · Cost 6,193.10 · Profit 5,356.90 · Margin 46.4%					
KIND	DESCRIPTION	CALC (TAKE-OFF)	QTY	UNIT	UNIT COST	COST	UNIT SELL	SELL
LABOUR	Joinery installer installer · PLACEHOLDER	1 x (2 + 2.4 m x 4.5 h/m) +10% site access allowance	14.08	h	23.40	329.47	60.00	844.80
MATERIAL	Egger MFC 18 mm 2800 x 2070 mfc_18 · PLACEHOLDER	wardrobe x1: 13.27 m² of parts / (5.8 m² sheet x 84% yield)	2.73	sheet	250.00	681.63	375.00	1,022.44
MATERIAL	MDF 6 mm 1220 x 2440 (backs, drawer bottoms) mdf_06 · PLACEHOLDER	wardrobe x1: 4.5 m² of parts / (2.98 m² sheet x 85% yield)	1.78	sheet	35.00	62.25	52.50	93.37
MATERIAL	PVC edge band 0.8 mm (carcass) edge_band_thin · PLACEHOLDER	16.5 m carcass edges + 10%	18.15	m	0.55	9.98	0.83	14.97
MATERIAL	PVC edge band 2 mm (fronts) edge_band_thick · PLACEHOLDER	23.6 m front edges + 10%	25.96	m	1.40	36.34	2.10	54.52
MATERIAL	Soft-close concealed hinge hinge_soft_close · PLACEHOLDER	4 doors x 5 hinges (2.5 m high)	20	pc	15.00	300.00	22.50	450.00
MATERIAL	Bar handle 160 mm handle_std · PLACEHOLDER	4 fronts	4	pc	15.00	60.00	22.50	90.00
MATERIAL	Shelf support pin shelf_pin · PLACEHOLDER	4 shelves x 4 pins	16	pc	0.30	4.80	0.45	7.20
MATERIAL	Oval wardrobe rail hanging_rail · PLACEHOLDER	0.9 m rail	0.9	m	15.00	13.50	22.50	20.25
MATERIAL	Adjustable cabinet leg adjustable_leg · PLACEHOLDER	6 adjustable legs	6	pc	4.00	24.00	6.00	36.00
LABOUR	Carpenter (workshop) carpenter · PLACEHOLDER	1 x (5 setup + 17.77 m² x 1.0 + 4 doors x 1.0 + 0 drawers x 1.5 + 4 shelves x 0.3)	27.97	h	21.60	604.25	55.00	1,538.59
LABOUR	Joinery installer installer · PLACEHOLDER	1 x (2 + 1.8 m x 4.5 h/m) +10% site access allowance	11.11	h	23.40	259.97	60.00	666.60
Line totals						5,045.57		9,765.83
Item cost total 6,193.10 · materials 2,998.15 · labour 2,047.43 · sell build-up 9,765.82 · client amount 11,550.00 Labour hours: electrician 4.1 h, carpenter 63.5 h, installer 25.2 h								

07 Dresser & Vanity Mirror · Master Bedroom					Client AED 3,000 · Cost 1,622.88 · Profit 1,377.12 · Margin 45.9%			
Kind	Description	Calc (Take-off)	Qty	Unit	Unit Cost	Cost	Unit Sell	Sell
MATERIAL	Egger MFC 18 mm 2800 x 2070 mfc_18 · PLACEHOLDER	dresser x1: 4.94 m² of parts / (5.8 m² sheet x 84% yield)	1.01	sheet	250.00	253.66	375.00	380.48
MATERIAL	MDF 6 mm 1220 x 2440 (backs, drawer bottoms) mdf_06 · PLACEHOLDER	dresser x1: 1.82 m² of parts / (2.98 m² sheet x 85% yield)	0.72	sheet	35.00	25.23	52.50	37.85
MATERIAL	PVC edge band 0.8 mm (carcass) edge_band_thin · PLACEHOLDER	11.36 m carcass edges + 10%	12.5	m	0.55	6.87	0.83	10.31
MATERIAL	PVC edge band 2 mm (fronts) edge_band_thick · PLACEHOLDER	7.68 m front edges + 10%	8.45	m	1.40	11.83	2.10	17.74
MATERIAL	Soft-close full-extension runner (pair) drawer_runner · PLACEHOLDER	4 drawers	4	pair	45.00	180.00	67.50	270.00
MATERIAL	Bar handle 160 mm handle_std · PLACEHOLDER	4 fronts	4	pc	15.00	60.00	22.50	90.00
LABOUR	Carpenter (workshop) carpenter · PLACEHOLDER	1 x (2 setup + 6.76 m² x 1.0 + 0 doors x 1.0 + 4 drawers x 1.5 + 0 shelves x 0.3)	14.76	h	21.60	318.90	55.00	812.01
LABOUR	Joinery installer installer · PLACEHOLDER	1 x (1.5 + 1.2 m x 1.5 h/m) +10% site access allowance	3.63	h	23.40	84.94	60.00	217.80
MATERIAL	Clear silver mirror 5 mm mirror_clear_5mm · PLACEHOLDER	1 x 0.9 x 1.2 m + 10%	1.19	m2	80.00	95.04	116.00	137.81
MATERIAL	Mirror edge polishing mirror_edge_polish · PLACEHOLDER	1 x perimeter 4.2 m (polished)	4.2	m	7.00	29.40	10.15	42.63
MATERIAL	Mirror adhesive cartridge mirror_adhesive · PLACEHOLDER	mirror adhesive	1.08	pc	25.00	27.00	36.25	39.15
MATERIAL	LED strip 24 V 10 W/m 3000K led_strip_24v · PLACEHOLDER	3.78 m x 1 run(s) + 5% = 3.97 m	3.97	m	9.00	35.72	14.40	57.15
MATERIAL	LED driver 24 V 60 W led_driver_60w · PLACEHOLDER	37.8 W (3.78 m x 10 W/m) at 80% max load	1	pc	40.00	40.00	64.00	64.00
MATERIAL	LED feed connector / end caps / clips kit led_connector_kit · PLACEHOLDER	1 feed point(s)	1	pc	6.00	6.00	9.60	9.60
MATERIAL	Single-core cable 1.5 mm² (coil 91.4 m) cable_1_5 · PLACEHOLDER	1 feeds x 6 m	6	m	1.53	9.18	2.45	14.69
LABOUR	Electrician electrician · PLACEHOLDER	3.97 m strip, 1 driver(s) +10% site access allowance	1.7	h	21.60	36.68	60.00	101.89
MATERIAL	Touch / door sensor switch led_sensor · PLACEHOLDER	touch sensor switch	1	pc	25.00	25.00	40.00	40.00

07 Dresser & Vanity Mirror · Master Bedroom						Client AED 3,000 · Cost 1,622.88 · Profit 1,377.12 · Margin 45.9%		
KIND	DESCRIPTION	CALC (TAKE-OFF)	QTY	UNIT	UNIT COST	COST	UNIT SELL	SELL
LABOUR	Carpenter (workshop) carpenter · PLACEHOLDER	stand-off backing frame	1.5	h	21.60	32.40	55.00	82.50
LABOUR	Joinery installer installer · PLACEHOLDER	1 x (0.75 h + 1.08 m² x 0.9 h/m²) +10% site access allowance	1.89	h	23.40	44.32	60.00	113.65
Line totals						1,322.17		2,539.26
Item cost total 1,622.88 · materials 804.93 · labour 517.25 · sell build-up 2,539.26 · client amount 3,000.00 Labour hours: carpenter 16.3 h, installer 5.5 h, electrician 1.7 h								

08 Gypsum Partition · Living Room						Client AED 850 · Cost 465.68 · Profit 384.32 · Margin 45.2%		
KIND	DESCRIPTION	CALC (TAKE-OFF)	QTY	UNIT	UNIT COST	COST	UNIT SELL	SELL
MATERIAL	Gypsum board 1200 x 2400 x 12.5 mm gypsum_board_std · PLACEHOLDER	6.72 m² x 2 face(s) + 10%	5.13	sheet	22.00	112.93	29.70	152.46
MATERIAL	Metal C-stud 70 mm x 3 m stud_c · PLACEHOLDER	5 studs @ 0.6 m (+2 per door) x 1 length(s)	5	pc	10.00	50.00	13.50	67.50
MATERIAL	Metal U-track 72 mm x 3 m track_u · PLACEHOLDER	top + bottom 2 x 2.4 m + door heads	1.68	pc	9.50	15.96	12.83	21.55
MATERIAL	Drywall screws 25 mm drywall_screws · PLACEHOLDER	boards: 13.44 m² x 15 screws/m²	201.6	pc	0.04	9.07	0.06	12.25
MATERIAL	Paper joint tape joint_tape · PLACEHOLDER	boards: 13.44 m² x 1.25 m/m²	16.8	m	0.23	3.86	0.31	5.22
MATERIAL	Joint compound 28 kg joint_compound · PLACEHOLDER	boards: 13.44 m² x 0.4 kg/m²	0.19	bag	57.50	11.04	77.62	14.90
LABOUR	Gypsum carpenter gypsum · PLACEHOLDER	6.72 m²: framing 0.35 + boarding 0.2 x 2 + finishing 0.225 x 2 h/m² +10% site access allowance	8.87	h	19.90	176.52	50.00	443.52
Line totals						379.38		717.40
Item cost total 465.68 · materials 202.87 · labour 176.52 · sell build-up 717.39 · client amount 850.00 Labour hours: gypsum 8.9 h								

09 Electrical Points					Client AED 3,100 · Cost 1,564.75 · Profit 1,535.25 · Margin 49.5%			
KIND	DESCRIPTION	CALC (TAKE-OFF)	QTY	UNIT	UNIT COST	COST	UNIT SELL	SELL
MATERIAL	13 A twin switched socket socket_double_13a · PLACEHOLDER	6 x socket	6	pc	40.00	240.00	64.00	384.00
MATERIAL	GI back box 3 x 3 back_box · PLACEHOLDER	6 back boxes	6	pc	1.75	10.50	2.80	16.80
MATERIAL	Single-core cable 2.5 mm² (coil 91.4 m) cable_2_5 · PLACEHOLDER	6 x 24 m avg run	144	m	2.19	315.36	3.50	504.58
MATERIAL	PVC conduit 20 mm x 3 m conduit_20 · PLACEHOLDER	48 m conduit	16	pc	7.50	120.00	12.00	192.00
OTHER	Making good (plaster patch & touch-up) other	6 points	6	pt	15.00	90.00	22.50	135.00
LABOUR	Electrician electrician · PLACEHOLDER	6 x 3.5 h (new) +10% site access allowance	23.1	h	21.60	498.96	60.00	1,386.00
Line totals						1,274.82	2,618.38	
Item cost total 1,564.75 · materials 685.86 · labour 498.96 · other 90.00 · sell build-up 2,618.38 · client amount 3,100.00								
Labour hours: electrician 23.1 h								

10 Painting · Whole apartment					Client AED 4,350 · Cost 2,711.83 · Profit 1,638.17 · Margin 37.7%			
Kind	Description	Calc (Take-off)	Qty	Unit	Unit Cost	Cost	Unit Sell	Sell
MATERIAL	Interior emulsion (Jotun Fenomastic class) paint_emulsion · PLACEHOLDER	walls 240.66 m² x 2 coats / 9 m²/L + 5%	56.15	l	15.60	876.00	21.06	1,182.60
MATERIAL	Wall putty 20 kg wall_putty · PLACEHOLDER	walls 240.66 m² x 0.2 kg/m² (light prep)	2.41	bag	35.00	84.23	47.25	113.71
LABOUR	Painter painter · PLACEHOLDER	walls 240.66 m² x (0.06 h x 2 coats + 0.04 h prep) +10% site access allowance	42.36	h	17.50	741.23	35.00	1,482.47
MATERIAL	Ceiling emulsion matt paint_ceiling · PLACEHOLDER	ceilings 84.86 m² x 2 coats / 10 m²/L + 5%	17.82	l	8.50	151.48	11.48	204.49
MATERIAL	Wall putty 20 kg wall_putty · PLACEHOLDER	ceilings 84.86 m² x 0.2 kg/m² (light prep)	0.85	bag	35.00	29.70	47.25	40.10
LABOUR	Painter painter · PLACEHOLDER	ceilings 84.86 m² x (0.06 h x 2 coats + 0.04 h prep) x 1.25 +10% site access allowance	18.67	h	17.50	326.71	35.00	653.42
Line totals						2,209.35		3,676.79
Item cost total 2,711.83 · materials 1,141.41 · labour 1,067.94 · sell build-up 3,676.79 · client amount 4,350.00								
Labour hours: painter 61 h								

Purchase list

WHAT TO BUY · GROUPED BY CATEGORY · AMOUNTS IN AED

REF	DESCRIPTION	QTY REQUIRED	QTY TO BUY	UNIT	PACK NOTE	UNIT COST	COST	SUPPLIER
BOARDS · 4 ITEMS							3,355.00	
mdf_06	MDF 6 mm 1220 x 2440 (backs, drawer bottoms) • PLACEHOLDER PRICE	7.68	8	sheet		35.00	280.00	—
mfc_18	Egger MFC 18 mm 2800 x 2070 • PLACEHOLDER PRICE	10.15	11	sheet		250.00	2,750.00	—
ply_12	Plywood 12 mm 1220 x 2440 • PLACEHOLDER PRICE	1	1	sheet		85.00	85.00	—
ply_18	Marine plywood 18 mm 1220 x 2440 • PLACEHOLDER PRICE	1.68	2	sheet		120.00	240.00	—
CLADDING · 7 ITEMS							3,557.20	
cladding_adhesive	Panel adhesive cartridge • PLACEHOLDER PRICE	19.32	20	pc		18.00	360.00	—
cladding_trim	WPC / aluminium trim 2.9 m • PLACEHOLDER PRICE	5.54	6	pc		18.00	108.00	—
pvc_marble_sheet	PVC marble sheet 1220 x 2800 x 3 mm • PLACEHOLDER PRICE	4	4	sheet		170.00	680.00	—
pvc_trim	PVC / aluminium edge trim 2.9 m • PLACEHOLDER PRICE	9.56	10	pc		18.00	180.00	—
stone_pvc_panel	Stone-finish PU/PVC panel 1200 x 600 mm • PLACEHOLDER PRICE	13	13	pc		85.00	1,105.00	—
timber_batten	Timber batten 25 x 50 mm • PLACEHOLDER PRICE	11.2	11.2	m		3.50	39.20	—
wpc_fluted_panel	WPC fluted panel 160 x 2900 mm • PLACEHOLDER PRICE	31	31	pc		35.00	1,085.00	—
ELECTRICAL · 5 ITEMS							785.16	
back_box	GI back box 3 x 3 • PLACEHOLDER PRICE	6	6	pc		1.75	10.50	—
cable_1_5	Single-core cable 1.5 mm² (coil 91.4 m) • PLACEHOLDER PRICE	60	60	m		1.53	91.80	—
cable_2_5	Single-core cable 2.5 mm² (coil 91.4 m) • PLACEHOLDER PRICE	144	144	m		2.19	315.36	—
conduit_20	PVC conduit 20 mm x 3 m • PLACEHOLDER PRICE	17	17	pc		7.50	127.50	—

REF	DESCRIPTION	QTY REQUIRED	QTY TO BUY	UNIT	PACK NOTE	UNIT COST	COST	SUPPLIER
socket_double_13a	13 A twin switched socket • PLACEHOLDER PRICE	6	6	pc		40.00	240.00	—
FLOORING · 3 ITEMS							9,920.00	
skirting_pvc_80	PVC skirting 80 mm (2.4 m) • PLACEHOLDER PRICE	34.01	35	pc		29.00	1,015.00	—
spc_plank	SPC flooring plank 1800 x 180 mm	250.6	251	plank		35.00	8,785.00	—
threshold_profile	Aluminium threshold / transition profile 0.9 m • PLACEHOLDER PRICE	4	4	pc		30.00	120.00	—
GLASS · 3 ITEMS							175.40	
mirror_adhesive	Mirror adhesive cartridge • PLACEHOLDER PRICE	1.08	2	pc		25.00	50.00	—
mirror_clear_5mm	Clear silver mirror 5 mm • PLACEHOLDER PRICE	1.19	1.2	m2		80.00	96.00	—
mirror_edge_polish	Mirror edge polishing • PLACEHOLDER PRICE	4.2	4.2	m		7.00	29.40	—
GYPSUM · 7 ITEMS							938.78	
drywall_screws	Drywall screws 25 mm • PLACEHOLDER PRICE	687.96	688	pc		0.04	30.96	—
furring_channel	Furring channel 3 m • PLACEHOLDER PRICE	45.03	46	pc		9.10	418.60	—
gypsum_board_std	Gypsum board 1200 x 2400 x 12.5 mm • PLACEHOLDER PRICE	15.92	16	sheet		22.00	352.00	—
joint_compound	Joint compound 28 kg • PLACEHOLDER PRICE	0.67	1	bag		57.50	57.50	—
joint_tape	Paper joint tape • PLACEHOLDER PRICE	46.52	46.6	m		0.23	10.72	—
stud_c	Metal C-stud 70 mm x 3 m • PLACEHOLDER PRICE	5	5	pc		10.00	50.00	—
track_u	Metal U-track 72 mm x 3 m • PLACEHOLDER PRICE	1.68	2	pc		9.50	19.00	—
HARDWARE · 13 ITEMS							2,039.34	
adjustable_leg	Adjustable cabinet leg • PLACEHOLDER PRICE	14	14	pc		4.00	56.00	—
bed_gas_lift	Bed gas-lift mechanism (pair) • PLACEHOLDER PRICE	1	1	set		150.00	150.00	—

REF	DESCRIPTION	QTY REQUIRED	QTY TO BUY	UNIT	PACK NOTE	UNIT COST	COST	SUPPLIER
cable_grommet	Cable grommet • PLACEHOLDER PRICE	2	2	pc		5.00	10.00	—
drawer_runner	Soft-close full-extension runner (pair) • PLACEHOLDER PRICE	8	8	pair		45.00	360.00	—
edge_band_thick	PVC edge band 2 mm (fronts) • PLACEHOLDER PRICE	84.74	84.8	m		1.40	118.72	—
edge_band_thin	PVC edge band 0.8 mm (carcass) • PLACEHOLDER PRICE	78.34	78.4	m		0.55	43.12	—
floating_bracket	Concealed floating-shelf bracket • PLACEHOLDER PRICE	4	4	pc		25.00	100.00	—
handle_std	Bar handle 160 mm • PLACEHOLDER PRICE	15	15	pc		15.00	225.00	—
hanging_rail	Oval wardrobe rail • PLACEHOLDER PRICE	2.5	2.5	m		15.00	37.50	—
hinge_soft_close	Soft-close concealed hinge • PLACEHOLDER PRICE	45	45	pc		15.00	675.00	—
shelf_pin	Shelf support pin • PLACEHOLDER PRICE	40	40	pc		0.30	12.00	—
tv_bracket	TV wall bracket (fixed/tilt) • PLACEHOLDER PRICE	1	1	pc		120.00	120.00	—
wall_hanger	Concealed cabinet wall hanger • PLACEHOLDER PRICE	11	11	pc		12.00	132.00	—
LIGHTING · 7 ITEMS							1,250.00	
led_connector_kit	LED feed connector / end caps / clips kit • PLACEHOLDER PRICE	10	10	pc		6.00	60.00	—
led_driver_100w	LED driver 24 V 100 W • PLACEHOLDER PRICE	1	1	pc		60.00	60.00	—
led_driver_300w	LED driver 24 V 300 W • PLACEHOLDER PRICE	2	2	pc		130.00	260.00	—
led_driver_60w	LED driver 24 V 60 W • PLACEHOLDER PRICE	3	3	pc		40.00	120.00	—
led_profile	Aluminium LED profile + diffuser 2 m • PLACEHOLDER PRICE	7.4	8	pc		20.00	160.00	—
led_sensor	Touch / door sensor switch • PLACEHOLDER PRICE	2	2	pc		25.00	50.00	—
led_strip_24v	LED strip 24 V 10 W/m 3000K • PLACEHOLDER PRICE	59.3	60	m	12 rolls of 5	9.00	540.00	—

REF	DESCRIPTION	QTY REQUIRED	QTY TO BUY	UNIT	PACK NOTE	UNIT COST	COST	SUPPLIER
PAINT · 3 ITEMS							1,416.20	
paint_ceiling	Ceiling emulsion matt • PLACEHOLDER PRICE	17.82	18	l	1 18 L pails of 18	8.50	153.00	—
paint_emulsion	Interior emulsion (Jotun Fenomastic class) • PLACEHOLDER PRICE	56.15	72	l	4 18 L pails of 18	15.60	1,123.20	—
wall_putty	Wall putty 20 kg • PLACEHOLDER PRICE	3.26	4	bag		35.00	140.00	—
UPHOLSTERY · 3 ITEMS							272.95	
batting	Polyester batting / wadding • PLACEHOLDER PRICE	2.88	2.9	m2		8.00	23.20	—
foam_50mm	High-density foam 50 mm • PLACEHOLDER PRICE	2.64	2.7	m2		42.50	114.75	—
upholstery_fabric	Upholstery fabric 140 cm • PLACEHOLDER PRICE	2.96	3	m		45.00	135.00	—
Total purchase list							23,710.03	

Joinery board usage

WOOD USED

REF	BOARD	AREA M²	SHEETS EXACT	SHEETS TO BUY	YIELD
mfc_18	Egger MFC 18 mm 2800 x 2070	49.4	10.2	11	92%
mdf_06	MDF 6 mm 1220 x 2440 (backs, drawer bottoms)	19.4	7.7	8	96%
ply_12	Plywood 12 mm 1220 x 2440	2.5	1	1	100%
ply_18	Marine plywood 18 mm 1220 x 2440	4.0	1.7	2	84%
Total		75.3	20.5	22	93%

Preliminaries

AMOUNTS IN AED

ITEM	CALC	COST	SELL
Transport & delivery	7 trips x AED 300	2,100.00	2,520.00
Floor & site protection	84.86 m² x AED 6 (min 250)	509.16	610.99
Final cleaning	84.86 m² x AED 3 (min 300)	300.00	360.00
Debris & packaging removal	base	300.00	360.00
Site supervision & coordination	27.42 h (13.71 site days x 2 h)	997.95	2,193.30
Building NOC / management fees	pass-through at cost	500.00	500.00
Total		4,707.11	6,544.29

Labour by trade

AMOUNTS IN AED

TRADE	HOURS	DAYS	COST / H	COST	SELL / H	SELL
Carpenter (workshop)	119	14.9	21.60	2,569.32	55.00	6,542.25
Gypsum carpenter	85.3	12.2	19.90	1,697.44	50.00	4,264.92
Joinery installer	77.3	11	23.40	1,808.80	60.00	4,637.95
Painter	61	8.7	17.50	1,067.94	35.00	2,135.89
Electrician	44.2	6.3	21.60	954.70	60.00	2,651.93
Flooring installer	38.7	5.5	19.90	770.26	50.00	0.00
Upholsterer (workshop)	8.5	1.1	21.60	183.86	55.00	468.16
Total	434	59.7		9,052.32		20,701.10

Schedule

WORKING DAYS

STAGE	DAYS
Procurement	5
Workshop	8
Site	13.7
Total days	19
Weeks	3.1

- Workshop crew 2, site crew 4, install crew 2; 8 h workshop / 7 h site days
- Longest site trade sets the pace (max 4 people on site)
- Site trades (gypsum, flooring, electrical, paint) run while joinery is in the workshop; joinery installation follows fabrication